ENGINEERING DEPARTMENT.

TUMKUR DIVISION.

Notification dated 5th January 1925.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division up to 12 noon on 29th January 1925, for constructing the Girls' School at Chiknayakanhalli. The work should be completed by the end of June 1926.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on all days except Sundays and other holidays.

3. Tenders should be submitted on special forms which can only be obtained from the Executive Engineer.

4. Each tender must be accompanied by a deposit of Rs. 250 (two hundred and fifty only) in cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing Girls' School at Chiknayakanhalli" in default of which, tenders will be rejected.

5. The acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in the due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned on surrendering the receipt granted therefor.

9. The rate should be noted both in figures and in words in the special form without any correction or addition under items of work.

10. No claim for any higher rate on any account will be entertained after the tender is accepted.

11. The contractor will be fined in terms of his bond for any short progress, or delay.

12. By failure to show the stipulated progress monthly, the tenderer will be liable for removal, fine and forfeiture of earnest money.

13. In matters of all disputes about rates, measurements, quality of work, etc., and in all disputes, of any kind the decision of the Chief Engineer will be final and legally binding.

14. Approximate estimate quantities for constructing Girls' School at Chiknayakanhalli. These quantities are not guaranteed.

Serial No.	Items of work	Per	Quantity	Rate
1	Earthwork excavation and filling in basement	C. yd.	78	
2	Burnt stone in clay	C. ft.	2,101	
3	Burnt brick in mortar	,,	1,329	
4	Burnt brick in clay	,,	3,593	
5	Burnt stone slabs 6" dressed and fixed	S. ft.	155	
6	Plastering with chunam	Sqr.	77·25	
7	White and colour washing	,,	77·25	
8	Honney wood work wrought and put up with wood oiling and tarring.	C. ft	138·14	
9	Roofing with Tumkur Tiles (Mangalore pattern) on teak reepers 2" x 1", etc.	Sqr.	23·62	
10	Ridge tiles set in mortar and pointed	R. ft.	140	
11	Teakwood battoned doors, with iron clamps, fastenings and fitting complete.	S. ft.	136	
12	Teakwood windows with ½" iron bars iron clamps, single side shutter battoned and half glazed with fastenings, etc.	,,	96	
13	Chocolate painting	Sqr.	5·13	
14	Flooring with Cudapah slabs over 3" concrete and cement pointing ..	,,	7·20	
15	Do 5" concrete and smooth plastering	,,	6·82	
16	Chunnam borders over gable	R. ft.	10	
17	Caps over gate pillars	No.	2	
18	Junglewood gate with iron fittings, etc.	,,	1	
19	Three-forth inches iron rod to tighten the rafters with bolts and nuts where purlins are placed in support of ridge piece	R. ft.	85	
20	Clearing site, levelling ground, etc...	L. S.	....	

V. V. KARVE,
Executive Engineer.